



© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910. ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.



ELEVATION

(B)



SECTION THRU WALL

(A)

- NOTE:
1. SLAB ON GRADE REINF. NOT SHOWN FOR CLARITY. SEE PLAN FOR REINF.
2. STUD WALL ANCHOR BOLTS NOT SHOWN FOR CLARITY. SEE PLAN.

STEMWALL OVER STEPPED FOOTING


SCALE: 1" = 1'-0"

11

CHANGE IN FOOTING THICKNESS

SCALE: 1" = 1'-0"

8



- NOTE:
1. SEE 8/4 AND 6/5/200 FOR ADDITIONAL INFO.

STEPPED PAD FTG. @ ELEVATOR PIT


SCALE: 1" = 1'-0"

9


TYPICAL PLANTER DETAIL

SCALE: 1" = 1'-0"

7




- NOTE:
1. SLAB ON GRADE NOT SHOWN FOR CLARITY




DEPRESSION UP TO 4"

(A)



DEPRESSION UP TO 12"

(B)



DEPRESSION UP TO 24"


(C)



SLAB ON GRADE EDGE DETAIL


SCALE: 1" = 1'-0"

6




DEPRESSION UP TO 4"

(A)



DEPRESSION UP TO 12"

(B)



DEPRESSION UP TO 24"


(C)



SLAB ON GRADE EDGE DETAIL

SCALE: 1" = 1'-0"

6




- NOTES:
1. SEE SOILS REPORT FOR ADDITIONAL SUBGRADE PREPARATION REQUIREMENTS.
2. VAPOR BARRIER SPECS NOT PER GCA.

TYPICAL SLAB ON GRADE


SCALE: 1" = 1'-0"

1



CONTROL JOINT FOR CONTINUOUS POUR

(A)



CONSTRUCTION JOINT

(B)

- NOTES:
1. CONTROL JOINTS ARE TO BE LOCATED AT ALL COLUMN CENTER LINES AND AT 20'-0" O.C. MAX. AND EVERY 400 SF.
2. SAW CUT SLAB WITHIN 18 HOURS OF POUR.
3. AT CONTRACTOR'S OPTION, SPEED DOWELS MAY BE USED IN LIEU OF PAINTING BOND BREAKER ALONG KEY.

JOINTS AT SLAB ON GRADE

SCALE: 1" = 1'-0"


3



garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL, SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:



EXPIRATION DATE: 3/31/2026

PROJECT NAME:

MOORPARK -
AB1763

PROJECT ADDRESS:

12750 W MOORPARK
AVE
LOS ANGELES, CA

OWNER:

DAVID & MATTHEW
PARVIZYAR

10/6/2023	PC SUBMITTAL
DATE	ISSUE
ISSUE NO.:	PC RE-SUBMITTAL
ISSUE DATE:	5/10/2024
PROJECT NO.:	2023-05
CAD DWG FILE:	TD - CONC.DWG
DRAWN BY:	IGC
CHECKED BY:	IGC
SHEET TITLE:	

TYPICAL DETAILS

SHEET SCALE:

N.T.S.


S201

NOT USED

SCALE: 1" = 1'-0"

12


© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910. ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.



8'-0" MAX. OPENING

NOTES:

1. SEE "STUD WALL FRAMING ELEVATION AND NOTES" FOR MINIMUM HEADER SIZE, NUMBER AND SIZE OF TRIMMERS AND KING STUDS.



TYP. MINIMUM ROOF HEADER SCHEDULE U.N.O.
(FOR ROOF DECK SEE FLOOR HEADER SCHED.)

WIDTH OF OPENING	8'-0"	6'-0"	4'-0"
NUMBER OF TRIMMERS	1	1	1
*d' @ 4" WALLS	4x8	4x6	4x4
*d' @ 6" WALLS	6x6	6x6	6x6

TYP. MINIMUM FLOOR AND ROOF DECK HEADER SCHEDULE U.N.O.

WIDTH OF OPENING	8'-0"	6'-0"	4'-0"
NUMBER OF TRIMMERS	2	2	2
NON LOAD BEARING 4" 6"	4x8 6x8	4x8 6x6	4x6 6x6
1 LEVEL BEARING 4" 6"	4x16 6x12	4x12 6x10	4x8 6x6
2 LEVEL BEARING 4" 6"	4x16 6x14	4x12 6x10	4x8 6x8

N LEVEL BEARING: INDICATES "N" # OF LEVELS SUPPORTED BY THE HEADER
4": INDICATES 4" STUD WALL
6": INDICATES 6" STUD WALL

NOTES:

1. SEE PLANS FOR SPECIAL FRAMING REQUIREMENTS.
2. HEADER SIZES SHOWN IN SCHEDULES ABOVE ARE MINIMUM HEADER SIZES. SEE PLANS FOR WHERE LARGER HEADER SIZES ARE REQUIRED.
3. STUD HEIGHT LIMITATIONS:
 - 3.1. 2x4 AT 16" O.C. NOT TO EXCEED 9'-0".
 - 3.2. 3x4 AT 16" O.C. NOT TO EXCEED 10'-6".
4. TRIMMERS TO BE SAME SIZE AS STUDS AT GIVEN FLOOR LEVEL U.N.O. SEE PLANS FOR POSTS WHERE REQUIRED INSTEAD OF TRIMMERS.
5. SEE PLANS FOR SHEAR WALL FRAMING REQUIREMENTS.
6. FOR ACTUAL WALL WIDTH, SEE ARCHITECTURAL DRAWINGS.
7. FOR NON-BEARING STUD WALLS, USE 2x4 STUD AT 16" O.C. U.N.O.
8. ALIGN ROOF & FLOOR FRAMING WITH STUDS AS SHOWN.
9. IF CALLED OUT STUD SIZES AT ANY GIVEN FLOOR LEVEL EXCEED THESE LIMITATIONS, CONTACT STRUCTURAL ENGINEER FOR CLARIFICATION.

TYPICAL STUD WALL OPENING FRAMING



SCALE: 1" = 1'-0"

8

TYPICAL STUD WALL FRAMING ELEVATION AND NOTES

SCALE: 1" = 1'-0"

2



PERP. TO JOIST

PARALLEL TO JOIST

NOTES:

1. DETAIL APPLIES TO BOTH ENGINEERED AND SAWN LUMBER. SAWN LUMBER SHOWN.
2. FOR WALL ASSEMBLIES WITH HEAVIER FINISHES SUCH AS STONE VENEER, CLIP SPACING SHALL BE REDUCED BY HALF.

SCALE: 1" = 1'-0"

12

TOP CONN. @ NON BEARING WALL

9

BASE DETAIL @ NON SHEATHED WALL


SCALE: 1" = 1'-0"

6

TYPICAL POST BASE

SCALE: 1" = 1'-0"

3




WITHIN A WALL

ISOLATED POST

garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL. SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:



EXPIRATION DATE: 3/31/2026

PROJECT NAME:

MOORPARK -
AB1763

PROJECT ADDRESS:

12750 W MOORPARK
AVE
LOS ANGELES, CA

OWNER:

DAVID & MATTHEW
PARVIZYAR

10/6/2023 PC SUBMITTAL
DATE ISSUE
ISSUE NO.: PC RE-SUBMITTAL
ISSUE DATE: 5/10/2024
PROJECT NO.: 2023-05
CAD DWG FILE: TD - WD.DWG
DRAWN BY: IGC
CHECKED BY: IGC
SHEET TITLE:


TYPICAL DETAILS

SHEET SCALE:


1" = 1'-0"

S202

© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910. ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.



NOTES:
1. THIS DETAIL ADDRESSES THE CONNECTION OF THE HOIST BEAM TO A WOOD SHAFT WALL. IF A STEEL POST IS PROVIDED CENTERED ON THE HOIST BEAM THE HOIST BEAM CAN BE CONNECTED TO SUCH A POST ALTERNATIVELY TO THIS DETAIL.



NOTES:
1. WHERE WALL IS PARALLEL TO JOIST PROVIDE BLOCKING ON EA. SIDE OF TOP PL. SPLICE & BOTH SIDES OF WALL.

HOIST BEAM TO WOOD WALL


SCALE: 1" = 1'-0"

10

PIPE THRU SHEAR WALL TOP PLATES

SCALE: 1" = 1'-0"

7



TYP. STAIR STRINGER DETAIL


SCALE: 1" = 1'-0"

11

INTERRUPTED TOP PLATE SPLICE

SCALE: 1" = 1'-0"

8



NOTES:
1. SAWN LUMBER & TRUSS FRAMING SIMILAR.

TYP. STAIR STRINGER FOOTING

SCALE: 1" = 1'-0"

12

FRAMING AT NON BEARING WALLS

SCALE: 1" = 1'-0"

9

NAILING SCHEDULE	
CONNECTION	NAILING
POST TO PIER PAD, TOE NAIL	3-16d or 4-8d
GIRDER TO POST, TOE NAIL	3-16d or 4-8d
JOIST TO SILL OR GIRDER, TOE NAIL	3-8d
BRIDGING TO JOIST, TOE NAIL EACH END	2-8d
JOIST TO BLOCKING, END NAIL	16d T&B OF EACH JOIST
RIM JOIST TO JOISTS, END NAIL	16d T&B OF EACH JOIST
RIM JOIST TO SILL, TOE NAIL	16d @ 16" O.C.
JOIST LAP @ BEARING, FACE NAIL	2-16d
SOLE PLATE TO JOIST OR BLOCKING, FACE NAIL	16d @ 16" O.C.
TOP PLATE TO STUD, END NAIL	2-16d
STUD TO SOLE PLATE	2-16d END NAIL, OR 4-8d TOE NAIL
DOUBLED STUDS, FACE NAIL	16d @ 24" O.C.
DOUBLE TOP PLATES, FACE NAIL	8-16d
DOUBLE TOP PLATES, LAP SPLICE	16d @ 16" O.C.
TOP PLATES, LAPS AND INTERSECTIONS, FACE NAIL	2-16d
BLOCKING BETWEEN JOISTS OR RAFTERS TO TOP PLATE, TOENAIL	3-8d
RIM JOIST TO TOP PLATE, TOENAIL	8d @ 16" O.C.
CONT. HEADER, TWO PIECES	16d @ 16" O.C. ALONG EACH EDGE
CEILING JOIST TO PLATE, TOE NAIL	3-8d
CONT. HEADER TO STUD, TOE NAIL	4-8d
CEILING JOISTS, LAP OVER PARTITIONS, FACE NAIL	3-16d
CEILING JOIST TO PARALLEL RAFTER, FACE NAIL	3-16d
RAFTER TO RIDGE	3-8d
RAFTER TIES, 2" LUMBER, FACE NAIL	3-16d
RAFTER TIES, 1" LUMBER, FACE NAIL	5-8d
RAFTER TO PLATE, TOE NAIL	3-8d
1"x4" MIN. BRACE TO EACH STUD AND PLATE, FACE NAIL	2-8d
BUILT-UP CORNER STUDS	16d @ 24" O.C.


SCHEDULE

TOE NAIL INSTALLATION

NAILING SCHEDULE

SCALE: 1" = 1'-0"


5



BM TO POST FACE MOUNT CONNECTION

SCALE: 1" = 1'-0"


6




EXTERIOR & BEARING STUDS NON-BEARING STUDS



ELECTRICAL & PLUMBING PROTECTION



DBL. TOP PL (SILL PL SIM.)



JOISTS


NOTES:

- PENETRATIONS/NOTCHES SHOWN ON THIS SKETCH ARE PERMITTED ONLY FOR SINGLE SPAN, SIMPLY SUPPORTED BEAMS WITH UNIFORMLY DISTRIBUTED LOAD.
- OBTAIN ENGINEER'S APPROVAL IF CONCENTRATED LOADS ARE APPLIED TO THE BEAM SUCH AS COLUMNS ABOVE THE BEAM OR PERPENDICULAR BEAMS FRAMING INTO THE BEAM TO BE PENETRATED/NOTCHED.
- THIS DETAIL APPLIES TO SAWN LUMBER. FOR ENGINEERED LUMBER (INCLUDING TJI) REFER TO MANUFACTURER'S SPECIFICATIONS.
- HOLES AND NOTCHES SHALL NOT BE OVERCUT. IF OVERCUT, ENTIRE BEAM SHALL BE REPLACED AT CONTRACTOR'S EXPENSE.
- ONE (1) NOTCH OR PENETRATION ALLOWED IN END THIRDS OF SPAN ONLY.

TYPICAL NOTCHES & PENETRATIONS

SCALE: 1" = 1'-0"

2



NOTES:

- FOR COLUMN CAPS SPECS SEE "TYP. BEAM TO POST CONN. DETAIL".

TYP. STAIR STRINGER FOOTING

SCALE: 1" = 1'-0"

12

FRAMING AT NON BEARING WALLS

SCALE: 1" = 1'-0"

9

BM TO POST FACE MOUNT CONNECTION

SCALE: 1" = 1'-0"

6

TYPICAL KING POST DETAIL


SCALE: 1" = 1'-0"

3

garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL, SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:



EXPIRATION DATE: 3/31/2026

PROJECT NAME:

MOORPARK -
AB1763

PROJECT ADDRESS:

12750 W MOORPARK
AVE
LOS ANGELES, CA

OWNER:

DAVID & MATTHEW
PARVIZYAR

10/6/2023 PC SUBMITTAL
DATE ISSUE
ISSUE NO.: PC RE-SUBMITTAL
ISSUE DATE: 5/10/2024
PROJECT NO.: 2023-05
CAD DWG FILE:
DRAWN BY: IGC
CHECKED BY: IGC
SHEET TITLE:


TYPICAL DETAILS

SHEET SCALE:


1" = 1'-0"

S203


© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA). 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910 / ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.



TYP. JOIST TO STEEL BM CONNECTION SCALE: 1" = 1'-0" 10



TYP. BEAM TO BEAM CONNECTION SCALE: 1" = 1'-0" 11




INLINE BEAM TO POST IN WALL SCALE: 1" = 1'-0" 12


JOIST/BEAM SIZE	TOP FLANGE HANGER	FACE MOUNT HANGER ⁽¹⁾
2x6 THRU 2x16	LB ESR-2533 COLA R925801	LUS ESR-2549 COLA R925807
2-2x6 THRU 2-2x14	HUSTF ESR-2533 COLA R925801	LUS ESR-2549 COLA R925807
4x6 THRU 4x14	HUTF ESR-2533 COLA R925801	HUS ESR-2533 COLA R925801
I-JOIST / LVL / LSL TO WOOD BEAM UP TO 16" DEEP	ITS ESR-2615 COLA R925803	IUS ESR-2532 COLA R925801
PSL / LVL / LSL: 3 ½" - 5 ¼" WIDTH	HGLTV ESR-2615 COLA R925803	MGU ESR-2532 COLA R925801
PSL / LVL / LSL: > 5 ¼" WIDTH	EGQ ESR-2615 COLA R925803	HGU ESR-2532 COLA R925801
ALL GLULAM U.N.O.	EGQ ESR-2615 COLA R925803	HHGU ESR-2532 COLA R925801

NOTES:
1. ALL HANGERS TO BE MANUFACTURED BY SIMPSON STRONG-TIE.
2. U.N.O. PROVIDE TOP FLANGE HANGERS AT ALL CONNECTIONS. FACE MOUNT HANGERS SHALL BE ALLOWED ONLY WHERE SPECIFICALLY INDICATED ON THE PLANS OR DETAILS.
3. PROVIDE SKEWED OR SLOPED HANGERS AS REQUIRED.
4. PROVIDE OFFSET OR CONCEALED FLANGE HANGER AT EDGE CONDITIONS AS REQUIRED.


TYPICAL HANGER SCHEDULE SCALE: 1" = 1'-0" 7




TYP. JOIST TO BEAM CONNECTION SCALE: 1" = 1'-0" 8




DRAG BEAM TO SHEAR WALL - ROOF SCALE: 1" = 1'-0" 9




TYP. BEAM TO WALL CONNECTION SCALE: 1" = 1'-0" 4




TYP. BEAM TO POST CONNECTION SCALE: 1" = 1'-0" 5



DRAG LINE CONNECTION - ROOF SCALE: 1" = 1'-0" 6



DROP BEAM TO WALL CONNECTION SCALE: 1" = 1'-0" 1



STEEL COLUMN IN STUD WALL SCALE: 1" = 1'-0" 3



garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL, SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:


EXPIRATION DATE: 3/31/2026

PROJECT NAME:
**MOORPARK -
AB1763**

PROJECT ADDRESS:
**12750 W MOORPARK
AVE
LOS ANGELES, CA**

OWNER:
**DAVID & MATTHEW
PARVIZYAR**


10/6/2023	PC SUBMITTAL
DATE	ISSUE
ISSUE NO.:	PC RE-SUBMITTAL
ISSUE DATE:	5/10/2024
PROJECT NO.:	2023-05
CAD DWG FILE:	
DRAWN BY:	IGC
CHECKED BY:	IGC
SHEET TITLE:	

TYPICAL DETAILS

SHEET SCALE:
1" = 1'-0"

S204

© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910 / ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.




- NOTES:
1. PROVIDE THIS DETAIL ONLY WHERE SPECIFICALLY CALLED OUT ON PLAN.
 2. CONNECTION AND BRACING OF MECHANICAL UNIT TO PLATFORM BY OTHERS.
 3. PROVIDE AT LEAST ONE ROW OF CONTINUOUS 2x BLOCKING AT PLATFORM REGARDLESS OF MECHANICAL UNIT WIDTH.

RAISED MECHANICAL PLATFORM

SCALE: 1" = 1'-0"

10




- NOTES:
1. THIS DETAIL ADDRESSES THE CONNECTION OF MEMBERS FORMING A "SISTERED" OR "COMPOSITE" ASSEMBLY (JOISTS). NUMBER AND SIZE OF MEMBERS FORMING THE ASSEMBLY ARE AS SPECIFIED ON PLAN.

SISTERED JOIST

SCALE: 1" = 1'-0"


11



TYP. FLOOR / ROOF OPENING


SCALE: 1" = 1'-0"

12




ADJOINING PANEL EDGE NAILING

A




ADJOINING PANEL EDGE NAILING - BLOCKED

B




TYPICAL NAILING EDGE DISTANCES

C



EDGE NAILING - 3 ROWS OF FASTENERS

E4



BOUNDARY NAILING - 3 ROWS OF FASTENERS


E1

HIGH LOAD DIAPHRAGM NAILING

- NOTES:
1. PROVIDE MULTIPLE ROWS OF FASTENERS WHERE "HIGH LOAD DIAPHRAGM" IS INDICATED ON PLAN.
 2. DECREASE SPACING BETWEEN ROWS TO 3/8" MIN. WHERE REQUIRED TO MAINTAIN 3/8" MIN. EDGE DISTANCE.

TYPICAL SHEATHING ASSEMBLY - FLOOR / DECK / ROOF


JOIST BLOCKING SPACING PER FRAMING DETAILS (6'-0" O.C. MAX)



- NOTES:
1. SEE DIAPHRAGM SCHEDULE ON PLAN FOR WOOD STRUCTURAL PANEL GRADE AND THICKNESS.
 2. SEE DIAPHRAGM SCHEDULE ON PLAN FOR NAIL SIZE AND SPACING AT BOUNDARY NAILING (B.N.), EDGE NAILING (E.N.), AND FIELD NAILING (F.N.).
 3. TONGUE AND GROOVE WOOD STRUCTURAL PANELS SHALL NOT BE USED AS A SUBSTITUTE FOR PANEL EDGE BLOCKING IN "BLOCKED DIAPHRAGM".
 4. STAGGER ALL WOOD STRUCTURAL PANEL END JOINTS.
 5. FACE GRAIN OF WOOD STRUCTURAL PANELS SHALL BE PERPENDICULAR TO JOIST/RAFTERS.
 6. DIAPHRAGM SHALL BE OBSERVED BY EOR & INSPECTED PRIOR TO COVERING.
 7. MINIMUM THICKNESS OF PLYWOOD SHEATHING SHALL BE PER TABLE 2304.8(1) OF THE CALIFORNIA BUILDING CODE.
 8. WHERE NAIL SPACING REQUIRES 3x NOMINAL FRAMING, SISTERED 2x FRAMING MAY BE PROVIDED AT CONTRACTOR'S OPTION. FRAMING SHALL BE SISTERED W/ E.N. EACH SIDE.


DIAPHRAGM NAILING AND WOOD STRUCTURAL PANEL LAYOUT

D



EDGE NAILING - 2 ROWS OF FASTENERS

E1



BOUNDARY NAILING - 2 ROWS OF FASTENERS

E1

E

garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL, SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:
REGISTERED PROFESSIONAL ENGINEER
IVAN G. CASTRO
C 84846
CIVIL
STATE OF CALIFORNIA
EXPIRATION DATE: 3/31/2026

PROJECT NAME:
MOORPARK - AB1763

PROJECT ADDRESS:
12750 W MOORPARK AVE
LOS ANGELES, CA

OWNER:
DAVID & MATTHEW PARVIZYAR

10/6/2023	PC SUBMITTAL
DATE	ISSUE
ISSUE NO.:	PC RE-SUBMITTAL
ISSUE DATE:	5/10/2024
PROJECT NO.:	2023-05
CAD DWG FILE:	
DRAWN BY:	IGC
CHECKED BY:	IGC
SHEET TITLE:	

TYPICAL DETAILS


SHEET SCALE:
1" = 1'-0"

S205

SCALE: 1" = 1'-0"


3

© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910. ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.




FRAMING PARALLEL

A



FRAMING PERPENDICULAR

B



LTP4 INSTALLATION


D

ALTERNATE

D

NOTES:

1. AT CONTRACTOR'S OPTION, WOOD STRUCTURAL PANEL SHEATHING MAY BE INSTALLED PER INSET DETAIL 'B' IN LIEU OF LTP4 SHOWN IN INSET DETAIL 'A'.



SHEAR WALL SILL PL ANCHOR

SCALE: 1/2" = 1'-0"

1


SHEAR WALL AT FRAMED FLOOR

SCALE: 1" = 1'-0"

LTP4 INSTALLATION


SCALE: 1" = 1'-0"

4




WALL CORNER

K




SINGLE HD END CONDITION

J




EDGE NAILING

I




INTERSECTING WALL

H




DOUBLE HD END CONDITION

G




PANEL EDGES

F




INTERSECTING WALL

E




INTERSECTING WALL

D




INTERSECTING WALL

C



WALL CORNER

B



WALL CORNER

A

SHEAR WALL SCHEDULE (2019 CBC - 2015 AF&PA SDPWS - TABLE 4.3A)											
MARK	WOOD STRUCTURAL PANELS ⁽¹⁾ (5-PLY OR OSB U.N.O. ON THE PLANS)	NUMBER OF SIDES	NAILING		SHEAR CLIPS ⁽⁶⁾ (A35 OR LTP4)	SILL PL ATTACHMENT U.N.O.			WELDED THREADED STUDS (WHERE OCCURS)	ALLOW. SHEAR - SEISMIC LOADS (PLF)	(7)
			EDGE (E.N.)	FIELD (F.N.)		WD FLOOR ⁽⁵⁾	CONCRETE	POST INSTALLED ⁽⁸⁾			
	15/32" APA RATED SHEATHING (PI 32/16)	1	8d @ 6" O.C.	8d @ 12" O.C.	1 @ 16" O.C.	SDS @ 16" O.C.	5/8"Ø A.B. @ 48" O.C.	THDB62800 @ 48" O.C.	5/8"Ø @ 24" O.C.	280	235
	15/32" APA RATED SHEATHING (PI 32/16)	1	8d @ 4" O.C.	8d @ 12" O.C.	1 @ 16" O.C.	SDS @ 8" O.C.	5/8"Ø A.B. @ 40" O.C.	THDB62800 @ 40" O.C.	5/8"Ø @ 24" O.C.	430	361
	15/32" APA RATED STRUCT-I SHEATHING (PI 32/16)	1	10d @ 4" O.C.	10d @ 12" O.C.	1 @ 12" O.C.	SDS @ 8" O.C.	5/8"Ø A.B. @ 32" O.C.	THDB62800 @ 32" O.C.	5/8"Ø @ 24" O.C.	510	428
	15/32" APA RATED STRUCT-I SHEATHING (PI 32/16)	1	10d @ 3" O.C.	10d @ 12" O.C.	1 @ 8" O.C.	SDS @ 6" O.C.	5/8"Ø A.B. @ 24" O.C.	THDB62800 @ 24" O.C.	5/8"Ø @ 24" O.C.	665	559
	15/32" APA RATED STRUCT-I SHEATHING (PI 32/16)	1	10d @ 2" O.C.	10d @ 12" O.C.	1 @ 8" O.C.	SDS @ 4" O.C.	5/8"Ø A.B. @ 16" O.C.	THDB62800 @ 16" O.C.	5/8"Ø @ 24" O.C.	870	731
	15/32" APA RATED STRUCT-I SHEATHING (PI 32/16)	2	10d @ 3" O.C.	10d @ 12" O.C.	2 @ 8" O.C.	SDS @ 3" O.C.	5/8"Ø A.B. @ 16" O.C.	THDB62800 @ 12" O.C.	5/8"Ø @ 16" O.C.	1330	1117
	15/32" APA RATED STRUCT-I SHEATHING (PI 32/16)	2	10d @ 2" O.C.	10d @ 12" O.C.	2 @ 8" O.C.	2 ROWS SDS @ 4" O.C.	5/8"Ø A.B. @ 12" O.C.	THDB62800 @ 12" O.C.	5/8"Ø @ 12" O.C.	1740	1462


SHEAR WALL SCHEDULE NOTES:

1. FOR SHEAR WALL WITH ALLOWABLE SHEAR PER SCHEDULE EXCEEDING 350 PLF:
 - 1.1. PROVIDE 3x NOMINAL FRAMING AT ADJOINING PANEL EDGES (INCLUDING WALL STUDS AND BLOCKING).
 - 1.2. PROVIDE STAGGERED NAILING AT ALL PANEL EDGES.
2. AT DOUBLE SIDED SHEAR WALLS:
 - 2.1. ADJACENT PANEL EDGES SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS. SEE INSET DETAIL F-.
 - 2.2. SILL PLATE SHALL BE 3x NOMINAL WIDTH.
3. NAILS SHALL BE PLACED NOT LESS THAN 3/8" INCH FROM PANEL EDGES AT 2x MEMBERS (1/2" INCH AT 3x MEMBERS) & 3/8" INCH FROM THE EDGE OF THE STUDS AND BLOCKING. ALL SHEAR WALL NAILING SHALL UTILIZE COMMON NAILS OR GALVANIZED BOX.
4. FOR ALL WALLS, PROVIDE MINIMUM TWO ANCHOR BOLTS PER PIECE OF SILL PLATE & ONE LOCATED WITHIN 12" AND NOT LESS THAN 7 BOLT DIAMETERS FROM EACH END OF EACH SILL PLATE.
5. WOOD SCREWS SHALL BE SIMPSON SDS25600 FOR SILL PL CONNECTED TO WOOD RIM JOIST OR BLOCKING. PROVIDE SDS25412 FOR SILL PLATE CONNECTED TO TOP NAILER IN STEEL BEAMS.
6. WHEN LTP4 ARE USED, INSTALL LTP4 IN HORIZONTAL CONFIGURATION.
7. OSB OR PLYWOOD WOOD STRUCTURAL PANELS MAY BE USED FOR THE SHEAR WALL CONSTRUCTION, EXCEPT THAT OSB SHALL NOT BE PERMITTED IN SHEAR WALL CONSTRUCTION LABELED AS FIRE RETARDANT TREATED BY THE ARCHITECT. FOR FIRE RETARDANT TREATED SHEAR WALLS, THE UNIT SHEAR CAPACITY IS REDUCED TO 84% OF THE ALLOWABLE VALUE PER THE CODE REPORTS FOR THE SPECIFIED FIRE TREATMENT PRODUCT. SEE TIMBER GENERAL NOTES FOR ADDITIONAL INFORMATION.
8. WHERE TITEN HD SCREW ANCHORS ARE USED TO ANCHOR SILL PLATE TO EXISTING CONCRETE, MINIMUM EMBEDMENT IN CONCRETE SHALL BE 5 1/4".

garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL, SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:



EXPIRATION DATE: 3/31/2026

PROJECT NAME:

MOORPARK -
AB1763

PROJECT ADDRESS:

12750 W MOORPARK
AVE
LOS ANGELES, CA

OWNER:

DAVID & MATTHEW
PARVIZYAR

10/6/2023 PC SUBMITTAL
DATE ISSUE
ISSUE NO.: PC RE-SUBMITTAL
ISSUE DATE: 5/10/2024

PROJECT NO.: 2023-05
CAD DWG FILE: TD - SWHD.DWG
DRAWN BY: IGC
CHECKED BY: IGC

SHEET TITLE:

TYPICAL DETAILS

SHEET SCALE:

1" = 1'-0"



S206

SHEAR WALL SCHEDULE & END CONDITIONS

SCALE: 1" = 1'-0"

3

© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910. ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.



MARK (PER PLAN)	GRADE 36 ROD DIAM. "Da"	PL WASHER		HOLDOWN (1)	FASTENER	MIN POST SIZE (2)	CAPACITY	25% REDUCTION PER CITY OF LA
		T (IN)	SIDE (IN)					
2	3/8"	3/8"	1 1/2"	HDU2	6-SDS25212	4x4	3,075 LBS	2,306 LBS
4	3/8"	3/8"	1 1/2"	HDU4	10-SDS25212	4x4	4,565 LBS	3,424 LBS
5	3/8"	3/8"	1 1/2"	HDU5	14-SDS25212	4x6	5,670 LBS	4,253 LBS
8	7/8"	7/8"	2	HDU8	20-SDS25212	4x8 OR 6x6	7,890 LBS	5,918 LBS
11	1"	3/4"	2	HDU11	30-SDS25212	4x10 OR 6x6	9,535 LBS	7,151 LBS
14	1"	3/4"	2	HDU14	36-SDS25212	4x12 OR 6x6	14,390 LBS	10,793 LBS
12	1 1/8"	3/4"	2 1/2"	HD12	4-1"Ø BOLTS	4x8 OR 6x6	15,510 LBS	11,633 LBS
19	1 1/4"	3/4"	3	HD19	5-1"Ø BOLTS	4x8 OR 6x6	19,360 LBS	14,520 LBS

- NOTES:
1. HDU SCREW-STYLE HOLDOWNS ARE PER LARR #25720, ICC ESR 2330. BOLT-STYLE HOLD DOWNS PER LARR #25828, IAPMO ESR 0143.
 2. POST SIZE SHOWN ON THE SCHEDULE ARE MINIMUM SIZES. IF LARGER SIZES ARE SPECIFIED ON THE PLANS THE SIZES SHOWN ON PLANS SHALL BE USED.
 3. ROD SHALL BE A36 ALL THREADED RODS.
 4. NUT AT HOLDOWN THREADED ROD SHOULD BE FINGER-TIGHT PLUS 1/2 TURN WITH A HAND WRENCH. DO NOT OVER-TORQUE THE NUT. DO NOT USE IMPACT WRENCHES.
 5. HOLDOWN HARDWARE MUST BE SECURED IN PLACE PRIOR TO FOUNDATION INSPECTION/OBSERVATION.
 6. HOLDOWNS MUST BE INSPECTED/OBSERVED BEFORE COVERING WITH SHEATHING.
 7. HOLD-DOWN CONNECTOR BOLTS INTO WOOD FRAMING REQUIRE APPROVED PLATE WASHERS. CONNECTOR BOLTS INTO WOOD FRAMING REQUIRE STEEL PLATE WASHERS ON THE POST ON THE OPPOSITE SIDE OF THE ANCHORAGE DEVICE. PLATE SIZE SHALL BE A MINIMUM OF 0.299 INCH BY 3 INCHES BY 3 INCHES.


HOLDOWN ON STEEL BEAM

SCALE: 1" = 1'-0"



HOLDOWN SCHEDULE AND NOTES

SCALE: 1" = 1'-0"

1



- NOTE:
1. DETAIL SUBJECT TO CHANGE PENDING APPROVAL OF EBM SYSTEM.
 2. CONTRACTOR TO ACCOUNT FOR 4x POSTS & TIEDOWN STRAPS AT END OF EACH BEAM. POSTS TO CONTINUE TO BASE OF BUILDING.



EBM ROOF ANCHORAGE

SCALE: 1" = 1'-0"




HOLDOWN ON WOOD BEAM

SCALE: 1" = 1'-0"

HOLDOWN THRU WOOD FLOOR

SCALE: 1" = 1'-0"

2



MARK (PER PLAN)	GRADE 36 ROD DIAM. "Da"	HOLDOWN ANCHOR IN CONCRETE FOOTING		
		TYPE	"H" MIN	"Ca1" MIN "Ca2" MIN
2	3/8"	EDGE/FIELD	12"	4" NA
		CORNER	12"	4" 4"
4	3/8"	EDGE/FIELD	12"	4" NA
		CORNER	12"	4" 4"
5	3/8"	EDGE/FIELD	12"	4" NA
		CORNER	12"	4" 4"
8	7/8"	EDGE/FIELD	16"	4" NA
		CORNER	20"	4" 8"
11	1"	EDGE/FIELD	18"	4" NA
		CORNER	24"	4" 7"
14	1"	EDGE/FIELD	18"	4" NA
		CORNER	24"	4" 7"
12	1 1/8"	EDGE/FIELD	20"	4" NA
		CORNER	24"	12" 12"
19	1 1/4"	EDGE/FIELD	24"	4" NA
		CORNER	24"	15" 15"

HOLDOWN ANCHOR IN CONC. FOOTING

SCALE: 1" = 1'-0"

3

garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL, SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:
REGISTERED PROFESSIONAL ENGINEER
CIVIL
STATE OF CALIFORNIA
C 84846
EXPIRATION DATE: 3/31/2026

PROJECT NAME:

MOORPARK -
AB1763

PROJECT ADDRESS:

12750 W MOORPARK
AVE
LOS ANGELES, CA

OWNER:

DAVID & MATTHEW
PARVIZYAR

10/6/2023 PC SUBMITTAL
DATE ISSUE
ISSUE NO.: PC RE-SUBMITTAL
ISSUE DATE: 5/10/2024
PROJECT NO.: 2023-05
CAD DWG FILE: TD - SWHD.DWG
DRAWN BY: IGC
CHECKED BY: IGC
SHEET TITLE:

TYPICAL DETAILS

SHEET SCALE:


1" = 1'-0"

S207


© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910 / ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.

TIE DOWN SCHEDULE (KIPS)											
TIE DOWN TYPE		5TH TO ROOF		4TH TO 5TH		3RD TO 4TH		2ND TO 3RD		1ST TO 2ND	
		TENSION	COMPRESSION	TENSION	COMPRESSION	TENSION	COMPRESSION	TENSION	COMPRESSION	TENSION	COMPRESSION
1	TIE DOWN 1	2	3	3.5	7	5	12	8	18	12	24
2	TIE DOWN 2	4	5	8	10	15	18	23	27	33	39
3	TIE DOWN 3	4	5	10	12	21	22	29	32	41	45
4	TIE DOWN 4	8	9	18	22	32	37	45	52	58	62
5	TIE DOWN 5	4	5	8	10	15	18	23	27	-	-
6	TIE DOWN 6	7	9	16	21	27	35	40	52	-	-


- NOTES:
1. FOR ADDITIONAL TIE-DOWN DETAILS, SEE ZONE 4 SHEETS.
 2. ZONE 4 TIE-DOWN (ICC ESR-2190, LARR # 25623).
 3. SUBMIT MILL CERTIFICATES AND BILL OF LADING (SHIPPING HISTORY) TO THE BUILDING INSPECTOR FOR THE TIE DOWN RODS / ANCHOR BOLTS.
 4. CONTRACTOR TO VERIFY FLOOR TO FLOOR HEIGHT PRIOR TO ORDERING TIE-DOWN SYSTEM.
 5. CONTRACTOR TO SUBMIT TIE-DOWN SHOP DRAWING TO THE RECORD OF ENGINEER.




GRAPHICAL TIE DOWN REPRESENTATION




PLAN VIEW (C-BARS)




ELEVATION (A-BARS)



ISOMETRIC VIEW (A-BARS)



ELEVATION (D-BARS)




ELEVATION (B-BARS)

TIE-DOWN SCHEDULE


SCALE: 1" = 1'-0"

7

SUPPLEMENTAL REINFORCING BAR TYPES



TYP. TIE-DOWN ANCHOR
BASE ANCHORAGE - EDGE




TYP. TIE-DOWN ANCHOR
BASE ANCHORAGE - FIELD/INT.

NOTE
1. WHERE DISTANCE FROM TIEDOWN ANCHOR TO EDGE OF FOOTING IS LESS THAN 21", PROVIDE REINF. PER INSET DETAIL C/.

SUPPLEMENTAL REINFORCING SCHEDULE - FOOTINGS					
TIEDOWN RUN	A-BARS	B-BARS	C-BARS	D-BARS	ANCHOR PL
1	NO ADDITIONAL REINF. REQUIRED				4"x4"x1"
2	-	2-#5 EA. SIDE (4 TOTAL)	-	2-#5 E.S. EA. WAY (8 TOTAL)	
3	-	2-#5 EA. SIDE (4 TOTAL)	-	-	
4	3-#5	4-#5 EA. SIDE (8 TOTAL)	-	3-#5 E.S. EA. WAY (12 TOTAL)	

NOTE
1. "A-BARS" AND "B-BARS" ARE REQUIRED FOR ANCHORS NEAR AN EDGE ONLY.



NOTE
1. SLAB ON GRADE & WALL REINF. NOT SHOWN FOR CLARITY.

TIE-DOWN ANCHOR REINF.
IN CONCRETE WALL

DETAIL

SCALE: 1" = 1'-0"

DETAIL

SCALE: 1" = 1'-0"

8

DETAIL

SCALE: 1" = 1'-0"

DETAIL

SCALE: 1" = 1'-0"

9

TIE-DOWN SUPPLEMENTAL REINFORCING

SCALE: 1" = 1'-0"

3



garcia castro & associates inc.

CONSULTING STRUCTURAL ENGINEERS

750 Otay Lakes Rd #202
Chula Vista, CA 91910


e: garciacastro.se@gmail.com

www.gcastructural.com

CONSULTANTS

JZA ARCHITECTURE
4043 IRVING PL. SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:



EXPIRATION DATE: 3/31/2026

PROJECT NAME:

MOORPARK -
AB1763

PROJECT ADDRESS:

12750 W MOORPARK
AVE
LOS ANGELES, CA

OWNER:

DAVID & MATTHEW
PARVIZYAR

10/6/2023 PC SUBMITTAL

DATE ISSUE

ISSUE NO.: PC RE-SUBMITTAL

ISSUE DATE: 5/10/2024

PROJECT NO.: 2023-05

CAD DWG FILE: TD - SWHD.DWG

DRAWN BY: IGC

CHECKED BY: IGC


SHEET TITLE:

TYPICAL DETAILS

SHEET SCALE:


1" = 1'-0"

S208





BEAM CONNECTION SCHEDULE				
BEAM/ GIRDER	CONNECTION BOLT - A325X			
	NO. OF BOLTS	SIZE OF BOLTS	PLATE THICK. "t"	WELD SIZE "a", "b"
W6	2	5/8"Ø	3/8"	5/16"
W8, W10	2	7/8"Ø	3/8"	5/16"
W12, W14	3	7/8"Ø	3/8"	3/8"
W16, W18	4	7/8"Ø	1/2"	3/8"
W21	5	7/8"Ø	1/2"	3/8"
W24	6	7/8"Ø	1/2"	3/8"
W27	7	7/8"Ø	1/2"	3/8"
W30	8	7/8"Ø	5/8"	3/8"
W33	9	7/8"Ø	5/8"	3/8"
W36	10	7/8"Ø	5/8"	3/8"


- NOTES:
1. ALL FILLET WELD SIZES SHOWN ARE MINIMUM WELD SIZE. WHERE WELD SIZE SHOWN ARE SMALLER THAN AWS MINIMUM WELD SIZE, AWS MINIMUM WELD SIZE SHALL BE USED.
 2. FIELD WELD CONNECTION PLATES WHERE (N) MEMBERS CONNECT TO (E) MEMBERS.
 3. AT W6 BEAMS PROVIDE 1 1/2" SPACING BETWEEN BOLTS
 4. ALL HOLES SHALL BE STANDARD HOLES




NOT USED	SCALE: 1" = 1'-0"	10	NOT USED	SCALE: 1" = 1'-0"	7	HSS BASE PLATE	SCALE: 1" = 1'-0"	4	BEAM CONNECTION SCHEDULE	SCALE: 1" = 1'-0"
----------	-------------------	----	----------	-------------------	---	----------------	-------------------	---	--------------------------	-------------------



NOT USED	SCALE: 1" = 1'-0"	11	NOT USED	SCALE: 1" = 1'-0"	8	BEAM TO BEAM RIGID CONN.	SCALE: 1" = 1'-0"	5	TYP. BEAM TO BEAM CONNECTION	SCALE: 1" = 1'-0"	2
----------	-------------------	----	----------	-------------------	---	--------------------------	-------------------	---	------------------------------	-------------------	---



- NOTES:
1. WHERE INTERSECTING BEAM OCCURS, PROVIDE FULL DEPTH PLATE EACH SIDE OF WEB AS REQUIRED, SEE BEAM CONNECTION DETAILS.
 2. WHERE REQUIRED BY OTHER DETAILS, USE THE LARGER PL THICK./WELDS.
 3. FOR TUBE STEEL COLUMN ABOVE STEEL BEAM, USE INVERTED CONT. BM OVER COL. DETAIL.



NOT USED	SCALE: 1" = 1'-0"	12	NOT USED	SCALE: 1" = 1'-0"	9	HSS MEMBERS CONNECTION	SCALE: 1" = 1'-0"	6	TYP. TUBE STEEL COL. TO STL BEAM	SCALE: 1" = 1'-0"	3
----------	-------------------	----	----------	-------------------	---	------------------------	-------------------	---	----------------------------------	-------------------	---

PROJECT NAME:

**MOORPARK -
AB1763**

PROJECT ADDRESS:

**12750 W MOORPARK
AVE
LOS ANGELES, CA**

OWNER:

**DAVID & MATTHEW
PARVIZYAR**

10/6/2023	PC SUBMITTAL
DATE	ISSUE
ISSUE NO.:	PC RE-SUBMITTAL
ISSUE DATE:	5/10/2024
PROJECT NO.:	2023-05
CAD DWG FILE:	TD - STL.DWG
DRAWN BY:	IGC
CHECKED BY:	IGC
SHEET TITLE:	

TYPICAL DETAILS

SHEET SCALE:

1" = 1'-0"

S209

SHOP DRAWINGS DISCLAIMER

1. THESE SHOP DRAWINGS PROVIDE GENERAL CONFORMANCE WITH THE ENGINEER/ARCHITECT OF RECORD'S PROJECT DRAWINGS. DETAILS SHOWN HEREIN WERE PREPARED TO ACCOMMODATE THE PROJECT DRAWINGS. IN THE EVENT OF A CONFLICT BETWEEN THESE SHOP DRAWINGS AND THE PROJECT DRAWINGS, THE PROJECT DRAWINGS CONTROL.
2. MITek DID NOT PARTICIPATE IN THE PREPARATION OR REVIEW OF THE PROJECT DESIGN OR DRAWINGS, THEREBY MITek'S LIABILITY IS LIMITED TO THE DESIGN OF THE Z4 COMPONENTS AND THAT THE COMBINED COMPONENTS, AS SHOWN ON THE SHOP DRAWINGS, MEET APPLICABLE CODE REQUIREMENTS IN REGARD TO REPORTED CAPACITY AND DEFLECTION REQUIREMENTS.
3. PRIOR TO EOR'S APPROVAL OF Z4 SHOP DRAWINGS, THE FRAMER, CONTRACTOR AND/OR CUSTOMER IS RESPONSIBLE FOR ANY CONSTRUCTION, INSTALLATION, AND/OR SHIPMENT OF Z4 TIE-DOWN SYSTEM MATERIAL.
4. AFTER EOR'S APPROVAL OF Z4 SHOP DRAWINGS, MITek IS NOT RESPONSIBLE FOR ANY DEVIATION FROM THE RUN TYPE ELEVATIONS IN THIS SHOP DRAWING DURING CONSTRUCTION AND/OR INSTALLATION OF Z4 TIE-DOWN SYSTEM.

SCOPE OF WORK

1. WHEN APPLICABLE, Z4 TIE-DOWN SYSTEM LAYOUT PLANS (TDL) ARE PROVIDED TO COORDINATE THE RUN-TYPE NAMES INDICATED ON SHEET(S) Z4-02 TO Z4-03 WITH THE CORRESPONDING RUN-TYPE NAMES INDICATED ON THE STRUCTURAL DOCUMENTS. SEE ATTACHED TDL P SHEETS.
2. Z4 TIE-DOWN SYSTEM PROVIDED STARTS FROM THE COUPLER AT THE TOP OF THE EMBEDDED ANCHOR AND ABOVE, U.N.O.
3. BUILDING CODE: 2019 CBC
4. JURISDICTION: CITY OF LOS ANGELES
5. SHEETS Z4-01 TO Z4-03 REPLACE THE ORIGINAL TIE-DOWN SYSTEM SPECIFIED ON THE STRUCTURAL DOCUMENTS WITH THE MITek Z4 TIE-DOWN SYSTEM DESCRIBED BELOW.
6. FIRE-RETARDANT TREATED (FRT) LUMBER REQUIRED AS SHOWN WITHIN ARCHITECTURAL AND/OR STRUCTURAL DOCUMENTS. RUN-TYPES DESIGNED FOR FRT ARE INDICATED WITH (FRT) IN THE RUN-TYPE NAME AS SHOWN WITHIN THE Z4 ELEVATIONS.

SYSTEM DESCRIPTION

MITek Z4 IS A CONTINUOUS ROD TIE-DOWN SYSTEM USED IN WOOD FRAMED SHEAR WALLS CONSISTING OF CINCH NUT (CNX OR CNXO) DEVICES, STEEL ALL THREAD ROD (ATR), AND STEEL BEARING PLATE WASHERS (BPW). THE SYSTEM WILL RESIST SHEAR WALL UPLIFT WHILE COMPENSATING FOR SETTLEMENT, SHRINKAGE, AND COMPRESSION LOADING BY THE CONTINUAL DOWNWARD ACTION OF THE CNX DEVICES AS RECOGNIZED IN LA CITY RR 25623 AND ICC (ESR 2190) REPORTS.


GENERAL NOTES

1. ENGINEER OF RECORD (EOR)
- A. EOR SHALL VERIFY ALL CODE REQUIRED LOAD PARAMETERS AND LOAD TRANSFERS TO FOUNDATION. EOR'S APPROVAL OF THE ATTACHED Z4 TIE-DOWN SYSTEM DESIGNS ARE ONLY FOR VERIFICATION THAT THE LOAD VALUES (DEMANDS) USED BY MITek MEET THE EOR'S DESIGN INTENT AND THAT THE SYSTEM DETAILING SHOWN ON THESE SHOP DRAWINGS ARE IN GENERAL CONFORMANCE WITH THE EOR STRUCTURAL PLANS.
2. CINCH NUT (CNX/CNXO) - SEE DETAIL 1
- A. THE Z4 CINCH NUT IS A SHRINKAGE COMPENSATION DEVICE THAT CONNECTS THE WOOD FRAMING TO THE Z4 ROD TIE-DOWN SYSTEM. WHEN THE WOOD FRAMING SHRINKS OR SETTLES, THE CINCH NUT RATCHETS DOWN THE THREADS OF THE Z4 ROD SYSTEM TO PROVIDE PERPETUAL SHRINKAGE COMPENSATION.
- B. CINCH NUT IS IN COMPLIANCE WITH IBC 2009, 2012, 2015, 2018, 2020, 2019, 2021, 2024, 2017, 2020, TESTING OF THE CNX/CNXO IS IN ACCORDANCE WITH ICC-ES ESR-2190, RESEARCH REPORT, QUA LR 26623, ICC-ES REPORT ESR-2190.
- C. CINCH NUTS USED IN THE CONTINUOUS TIE-DOWN SYSTEM ATTACH TO THE WOOD WITH (2) MITek WS-3 SCREWS OR (2) 1/2" LAG SCREWS WITH MINIMUM THREAD INTO WOOD PENETRATION OF 1".
- D. CINCH NUT (CNX) AND CINCH NUT OMEGA (CNXO) MODELS ARE INTERCHANGEABLE.
3. BEARING PLATE WASHER (BPW) - SEE DETAIL 2
- A. Z4 BEARING PLATE WASHERS ARE PAINTED DIFFERENT COLORS TO VISUALLY DIFFERENTIATE LOAD CAPACITIES AND IMPROVE INSTALLATION ACCURACY.
- B. Z4 BEARING PLATE WASHERS ARE MANUFACTURED WITH STEEL MEETING ASTM A36, GB Q235, OR EQUIVALENT SPECIFICATIONS.
- C. Z4 BEARING PLATE WASHERS ARE REQUIRED TO BE INSTALLED TIGHT AGAINST THE WOOD TOP PLATE MEMBER.
4. COUPLER (CPL) NUT - SEE DETAIL 3
- A. SIGHT HOLES ARE PROVIDED WITH Z4 COUPLER NUTS TO ENSURE PROPER ROD INSTALLATION.
- B. CONTRACTOR TO VERIFY COUPLERS ARE THREADED HALF WAY INTO COUPLER FROM EACH SIDE.
- C. REDUCING COUPLER MAY BE REQUIRED AT FOUNDATION OR FLOOR TO FLOOR CONNECTIONS.
- D. REDUCING COUPLERS SHOULD HAVE THE LARGER DIAMETER ROD FULLY SEATED FIRST, BEFORE TIGHTENING THE SMALLER DIAMETER ROD.
- E. STANDARD (STD) COUPLERS CONFORM TO ASTM A-563 GRADE A, SAE GRADE 2.
- F. MID STRENGTH (MS) COUPLERS CONFORM TO ASTM A-563 GRADE C OR SAE GRADE 5 AND ARE DIFFERENTIATED WITH A SINGLE "SAW CUT" MARKING AS INDICATED IN DETAIL 3.
- G. HIGH STRENGTH (HS) COUPLERS CONFORM TO ASTM A-563 GRADE DH, ASTM A194-2H, OR SAE GRADE 8 AND ARE DIFFERENTIATED WITH A DOUBLE "SAW CUT" MARKING AS INDICATED IN DETAIL 3.
5. ALL THREAD ROD (ATR) - SEE DETAIL 4 & 6
- A. Z4 USES STANDARD GRADE AND HIGH STRENGTH ALL THREAD ROD (ATR). STANDARD GRADE ROD CONFORMS WITH ASTM A36. HIGH STRENGTH ROD CONFORMS WITH ASTM A193-87 AND IS IDENTIFIED BY RED PAINT ON THE ENDS AND CENTER WITH A STAMP LOCATED EITHER AT THE ENDS OR THE CENTER OF THE ROD.
- B. Z4 USES UNIFORM NATIONAL COARSE (UNC) THREADS FOR THE ROD.
- C. THREADED ROD INSTALLATION AT BOTTOM PLATE AND FLOOR FRAMING SHOULD USE OVERSIZE HOLES PER DETAIL 4 & 9. HOLES IN THE FLOOR FRAMING THAT ARE NOT OVERSIZED CAN BIND AND BOW THE ROD AS THE BUILDING SETTLES.
- D. MAXIMUM OUT OF PLUMB FOR ROD IS 2" FOR EVERY 100' OF FLOOR HEIGHT. (SEE DETAIL 8)
- E. 1ST FLOOR ROD CAN BE A LARGER DIAMETER THAN THE FOUNDATION ANCHOR AS THE DESIGN MAY BE CONTROLLED BY ELONGATION UNDER TENSION WHILE THE FOUNDATION ANCHOR MAY BE DESIGNED FOR TENSION ONLY.
6. FOUNDATION ANCHOR
- A. ANCHOR BOLT SHALL BE A MIN OF 8 INCHES TO A MAX OF 12 INCHES ABOVE CONCRETE U.N.O. ON TIE-DOWN ELEVATIONS.
- B. ACTUAL EXTENSION ABOVE CONCRETE SHALL BE VERIFIED PRIOR TO SHIPPING Z4 TIE-DOWN SYSTEM MATERIALS.
7. COMPRESSION POSTS - SEE DETAIL 7 & 8
- A. ENGINEER OF RECORD (EOR) SHALL CHECK COMPRESSION POST DESIGN CAPACITY FOR CONDITIONS SUBJECT TO ADDITIONAL LOADS SUCH AS BEAM OR HEADER REACTIONS.
- B. WHERE QUANTITY OF COMPRESSION POSTS ARE GREATER THAN THE SPACE BETWEEN ROD OR BEARING PLATE WASHER AND THE END OF THE SHEAR WALL, THE ADDITIONAL POSTS REQUIRED WILL BE ADDED TO THE OPPOSITE SIDE OF THE ROD.
- C. COMPRESSION POST SHALL BE OF SIZE, GRADE & SPECIES SPECIFIED. POSTS NOT SPECIFIED HEREIN SHALL BE THE RESPONSIBILITY OF THE EOR.
- D. THE COMPRESSION POSTS ON THE Z4 ELEVATIONS ARE DESIGNED TO THE WOOD SPECIES AND GRADE PER SHEET(S) N/A OF THE STRUCTURAL DOCUMENTS. THESE VALUES ARE SHOWN IN TABLE 7-0.
- E. THE WALL PLATES, USED FOR BPW AND CP DESIGN, ARE TO BE THE WOOD SPECIES AND GRADE SPECIFIED PER SHEET(S) N/A OF THE STRUCTURAL DOCUMENTS. THESE VALUES ARE SHOWN IN TABLE 7-1.


TABLE 7-0: COMPRESSION POST DESIGN CAPACITY FACTORS FOR FIRE-RETARDANT-TREATED WOOD									
TABLE 7-1: COMPRESSION POST DESIGN CAPACITY FACTORS FOR FIRE-RETARDANT-TREATED WOOD									
2x4: N/A	DF No. 2	F _o : 0.85	F _v : 0.88	2x4: N/A	4x6: DF No. 2	4x12: N/A	6x6: N/A	6x12: N/A	2x6: N/A
2x6: N/A	DF No. 2	F _o perp: 0.86	F _v : 0.88	3x4: N/A	4x4: N/A	2x6: DF No. 2	6x8: N/A	2x8: N/A	2x8: N/A
2x8: N/A	DF No. 2	FT: 0.84	E: 0.95	4x4: N/A	4x10: N/A	3x6: N/A	6x10: N/A		

ABBREVIATIONS


AB: ANCHOR BOLT	DIR: DIRECTION	N/A: NOT AVAILABLE / NOT APPLICABLE
AOR: ARCHITECT OF RECORD	EA: EACH	OC: ON CENTER
AT: ANCHOR TIE	EN: EDGE NAILING	OS: OVER-SIZED COUPLER HOLE
ATR: ALL THREADED ROD	EOR: ENGINEER OF RECORD	PL: PLATE
BPW: BEARING PLATE WASHER	F.F.: FINISHED FLOOR	QTY: QUANTITY
CP: CAST-IN-PLACE	FRT: FIRE-RETARDANT TREATED	RFI: REQUEST FOR INFORMATION
CL: CENTERLINE	E.G.: LATIN "FOR EXAMPLE"	SP: SOUTHERN YELLOW PINE
CMU: CONCRETE MASONRY UNIT	HDS: HOT-DIP GALVANIZED	SPF: SPRUCE-PINE-FIR
CNX: CINCH NUT	HF: HEM-FIR	STD: STANDARD
CNXO: CINCH NUT OMEGA	HS: HIGH STRENGTH	TDL: TIE-DOWN LAYOUT PLAN
CONST: CONSTRUCTION	HT: HEIGHT	TY: TYPICAL
CP: COMPRESSION POST(S)	LVL: LV: LEVEL	UNC: UNIFORM NATIONAL COARSE
CPL: COUPLER	MAX: MAXIMUM	U.N.O.: UNLESS NOTED OTHERWISE
DF: DOUGLAS-FIR LARCH	MIN: MINIMUM	WS: WOOD SCREW
DIA: DIAMETER	MS: MID STRENGTH	




1. CINCH NUT (CNX) INSTALLATION



5. TYPICAL Z4 TIE-DOWN SYSTEM INSTALLATION DETAIL



9. BRIDGE TERMINATION AT TOP LEVEL




ANCHOR TIE DEVICE	HEIGHT	WIDTH	DEPTH	3" [IN]	2CAPACITY [KIP]
AT-32	9	3 1/2	3	1/4	32.4
AT-32L	16	3 1/2	3	1/4	32.4
AT-65	11 3/4	4 1/4	3 1/2	5/16	64.8
AT-65L	16	4 1/4	3 1/2	5/16	64.8
AT-100L	16	4 3/4	3 3/4	3/8	100.0

13. ANCHOR TIE AT STEEL BEAM


MIN WALL THICKNESS	BEARING PLATE WASHER (BPW) DIMENSIONS [IN]				
	DESIGNATION	W	L	T	HOLE DIA
4"	BPW-5 (BROWN)	3	3	1/4	1 5/16
	BPW-6 (RED)	3 1/4	3 3/8	3/8	1 9/16
	BPW-7 (YELLOW)	3 1/4	4 3/8	1/2	1 9/16
	BPW-9 (GREEN)	3 1/4	5	5/8	1 9/16
	BPW-11 (BLUE)	3 1/4	5 7/8	3/4	1 9/16
	BPW-15 (BLACK)	3 1/4	7 7/8	7/8	1 9/16
	BPW-20 (WHITE)	3 1/4	10 1/4	1 1/4	1 9/16
	BPW-25 (ORANGE)	3 1/2	11 3/4	1 1/2	1 9/16
	BPW-30 (LIGHT GRAY)	3 1/2	14	1 3/4	1 9/16
	BPW-17-6 (LIGHT BLUE)	5	5 7/8	5/8	1 9/16
6"	BPW-27-6 (TAN)	5	9	1	1 9/16
	BPW-36-6 (GRAY)	5	12	1 1/2	1 9/16
	BPW-43-6 (PURPLE)	5	14	1 3/4	1 9/16
	BPW-46-6 (PINK)	5	15	1 7/8	1 9/16

- NOTES:
1. SEE DETAIL 1 FOR BPW DIMENSION DEFINITIONS.


2. BEARING PLATE WASHER (BPW) DIMENSIONS



6. ALLOWABLE ROD OFFSET




10. TOP PLATE TERMINATION




- NOTE:
- BEARING PLATE WASHER (BPW) TO MEET OR EXCEED "CUMULATIVE LOAD DEMAND" NOTED ON Z4 ELEVATIONS.


14. ANCHOR AT WOOD BEAM




3. COUPLER (CPL) NUT & DESCRIPTIONS




7. COMPRESSION POST LAYOUT




11. STRAP TERMINATION OPTION




15. POSTS OVER BPW




4. ATR TYPICAL ROD DIMENSIONS



8. COMPRESSION POST EDGE NAILING



12. TIE-DOWN SYSTEM LOAD PATH



NOT USED

0. DISCLAIMER, SCOPE OF WORK, SYSTEM DESCRIPTION, GENERAL NOTES, & ABBREVIATIONS

13. ANCHOR TIE AT STEEL BEAM


14. ANCHOR AT WOOD BEAM

15. POSTS OVER BPW


[illegible]

REVISION	DATE	DESCRIPTION
(1)	2023-12-19	EOR LOADING UPDATES
(2)	2024-02-15	EOR COMMENTS
Z4 PROJECT No.:	N/A	
SCALE:		
NOT TO SCALE		
ISSUE DATE (YYYY-MM-DD):		
2022-09-13		
DRAWN BY:		
TT		
CHECKED BY:		
RY		
SHEET No.:		
Z4-03		

LVL	CUMULATIVE TENSION LOAD (ASD) [lbs]		LEVEL TENSION LOAD (ASD) [lbs]	
	DEMAND	CAPACITY	DEMAND	CAPACITY
5	4000	6903	4000	4110
4	8000	9940	4000	4110
3	15000	17671	7000	7704
2	23000	27612	8000	9232




LVL	CUMULATIVE TENSION LOAD (ASD) [lbs]		LEVEL TENSION LOAD (ASD) [lbs]	
	DEMAND	CAPACITY	DEMAND	CAPACITY
5	7000	9940	7000	8958
4	16000	17671	9000	10735
3	27000	27612	11000	17161
2	40000	46595	13000	17161




NOT USED


COPYRIGHT 2021 GARCIA CASTRO & ASSOCIATES INC. (GCA) 750 OTAY LAKES RD. 202 CHULA VISTA, CA 91910 ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED ED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.




DETAIL SCALE: 1" = 1'-0" 10




DETAIL SCALE: 1" = 1'-0" 11




DETAIL SCALE: 1" = 1'-0" 12




DETAIL SCALE: 1" = 1'-0" 7




DETAIL SCALE: 1" = 1'-0" 8




DETAIL SCALE: 1" = 1'-0" 9




DETAIL SCALE: 1" = 1'-0" 4




DETAIL SCALE: 1" = 1'-0" 5




DETAIL SCALE: 1" = 1'-0" 6



DETAIL SCALE: 1" = 1'-0" 1



DETAIL SCALE: 1" = 1'-0" 2



DETAIL SCALE: 1" = 1'-0" 3



garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL, SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:

EXPIRATION DATE: 3/31/2026



PROJECT NAME:
MOORPARK - AB1763

PROJECT ADDRESS:
**12750 W MOORPARK AVE
LOS ANGELES, CA**

OWNER:
DAVID & MATTHEW PARVIZYAR

10/6/2023	PC SUBMITTAL
DATE	ISSUE
ISSUE NO.:	PC RE-SUBMITTAL
ISSUE DATE:	5/10/2024
PROJECT NO.:	2023-05
CAD DWG FILE:	S301.DWG
DRAWN BY:	IGC
CHECKED BY:	IGC
SHEET TITLE:	
DETAILS	
SHEET SCALE: 1" = 1'-0"	
S301	


© COPYRIGHT 2021, GARCIA CASTRO & ASSOCIATES INC. (GCA), 750 OTAY LAKES RD #202, CHULA VISTA, CA 91910 / ALL CONSTRUCTION DOCUMENTS SHALL REMAIN PROPERTY OF GCA. ALL UNAUTHORIZED USE, MODIFICATION OR REPRODUCTION IS PROHIBITED. GCA SHALL RETAIN ALL RIGHTS TO INTELLECTUAL PROPERTY CONTAINED HEREIN.

											
DETAIL	SCALE: 1" = 1'-0"	10	DETAIL	SCALE: 1" = 1'-0"	7	DETAIL	SCALE: 1" = 1'-0"	4	DETAIL	SCALE: 1" = 1'-0"	1
											
DETAIL	SCALE: 1" = 1'-0"	11	DETAIL	SCALE: 1" = 1'-0"	8	DETAIL	SCALE: 1" = 1'-0"	5	DETAIL	SCALE: 1" = 1'-0"	2
DETAIL	SCALE: 1" = 1'-0"	12	DETAIL	SCALE: 1" = 1'-0"	9	DETAIL	SCALE: 1" = 1'-0"	6	DETAIL	SCALE: 1" = 1'-0"	3



garcia castro & associates inc.
CONSULTING STRUCTURAL ENGINEERS
750 Otay Lakes Rd #202
Chula Vista, CA 91910
e: garciacastro.se@gmail.com
www.gcastructural.com

CONSULTANTS
JZA ARCHITECTURE
4043 IRVING PL. SUITE B
CULVER CITY, CA 90232
WWW.JZARCH.LA

STAMP:

EXPIRATION DATE: 3/31/2026

PROJECT NAME:
MOORPARK - AB1763

PROJECT ADDRESS:
12750 W MOORPARK AVE
LOS ANGELES, CA

OWNER:
DAVID & MATTHEW PARVIZYAR

10/6/2023	PC SUBMITTAL
DATE	ISSUE
ISSUE NO.:	PC RE-SUBMITTAL
ISSUE DATE:	5/10/2024
PROJECT NO.:	2023-05
CAD DWG FILE:	S302.DWG
DRAWN BY:	IGC
CHECKED BY:	IGC
SHEET TITLE:	
DETAILS	
SHEET SCALE:	
1" = 1'-0"	
S302	